



ARCHITECTURAL ALUMINIUM SYSTEMS  
Contemporary enclosures



# CORTIZO APP AVAILABLE ON GOOGLE PLAY AND APP STORE

**NEW APP**

AVAILABLE FOR SMART PHONE AND TABLET

Flexible technology, useful architecture.



experiment with  
**CORTIZO**

**CORTIZO RESPONSE**

{ TECHNICAL ASSISTANCE }  
{ SYSTEMS }

**DISCOVER CORTIZO**

{ AUGMENTED REALITY }  
{ COLOR EXPERIENCE }

**{ DOWNLOAD OUR APP }**



## CORTIZO AR DISCOVER AUGMENTED REALITY


1

Download our application using your platform and access Cortizo AR.




2

Focus the images identified by the AR logo. These images can be found equally in our catalogues as well as on our website.



3

Obtain a three dimensional view with all the luxury of the details of the main systems developed by CORTIZO.



## FAÇADES SYSTEMS

- 6 TP 52 Façade
- 8 SG 52 Façade
- 10 TPH 52 Façade
- 12 TPV 52 Façade
- 14 ST 52 Façade
- 16 SST 52 Façade
- 18 Equity Façade
- 20 Ventilated Façade
- 22 Millennium Façade
- 24 Solar Protection: Louvres
- 26 Lattices – Decorative Louvres

## COMPOSITE PANEL SYSTEM

## SKYLIGHT SYSTEMS – VERANDA – SLIDING ROOF SYSTEM

## WINDOW AND DOOR SYSTEMS HINGED

*With thermal break*

- 40 Cor-Urban CC
- 42 Cor-70 CC16
- 44 Cor-70 Hidden Sash CC16
- 46 Cor- Galicia Premium Aluminium/timber
- 48 Cor-80 Industrial
- 50 Cor-70 Industrial
- 52 Cor-70 Hidden Sash
- 54 Cor-60
- 56 Cor-3500
- 58 Millennium FR Door
- 60 Millennium Plus Door

*Without thermal break*

- 62 Cor-2000
- 64 Cor-2300
- 66 Millennium 2000 Door

## SLIDING WINDOW AND DOOR SYSTEMS

*With thermal break*

- 70 Cor-Vision Sliding
- 72 4600 Lift and Slide HI
- 74 4500 Lift and Slide
- 76 4200 Sliding

*Without thermal break*

- 78 2000 Perimetral Sliding

## SOLAR PROTECTION SYSTEMS

- 82 Tamiz

## BALUSTRADING SYSTEM

## 90 ACCESSORIES

## 94 DIRECTORIES

CORTIZO has consolidated itself as a leader in Architectural aluminium systems and in construction thanks to a determined investment strategy in R & D that has resulted in the creation of more than 50 latest generation window, façade and solar protection systems.

We create windows and façades that are made to measure for each architectural Project.

Creativity in order to respond to aesthetics and functionality for each style requirement.

Creativity with respect to living surroundings and to quality.

Apartments, family homes, hotels, offices, commercial centres, universities, concessionaries, museums...

### **CORTIZO Design**

### **QUALITY CERTIFICATIONS**

CORTIZO counts on the maximum quality certifications in the market: Qualicoat, Sea-Side, Qualideco, Ewaas-Euras, ISO 900, DIT, BBA, Wyrób budowlany, CSTB, CWCT, etc



To be able to achieve quality certification is for CORTIZO a non-negotiable condition with respect to its responsibilities to the market. For this reason the CORTIZO Technology Centre has been created and relies on 6 test benches to be able to test all the window, door and light façade systems.

AEV test benches (Air permeability, Water tightness and Wind resistance)

Thermal test bench

Acoustic test bench

Mechanical test bench

Light façade horizontal load resistance and impact test bench

Wind loading resistance for solar protection louvres and lattices test bench

### **CORTIZO certifies**

#### **ACOUSTIC INSULATION**

The R & D department has designed more than 50, latest generation, exclusive window, façade and solar protection systems that minimise the external acoustic contamination, ensuring comfort and intimacy in the home.

#### **CORTIZO silence**

#### **LEADERS IN THERMAL INSULATION**

Our enclosures optimise the energy saving in each home and incorporate the latest technological advances to form an insulation barrier that maximises savings in heating and air conditioning.

#### **CORTIZO energy efficiency**



### **SUSTAINABLE SPIRIT**

We use harmless products and raw materials in all our production processes, avoiding environmental risks just as much as in their transportation as their production.

CORTIZO Recycling has 2,100 recycling points strategically situated in order to close the circle ensuring a 100 per cent re-use and recycling of its aluminium.

### **CORTIZO sustainability**

#### **CORTIZO LAB**

In order to help the work of all the agents involved in a project, CORTIZO has created CORTIZO LAB, an on-line computing application ([www.cortizo.com](http://www.cortizo.com)) that serves as a virtual test laboratory in order to check the requirements established.

CORTIZO LAB allows the user to obtain automatically and on-line, tests, results and classifications of all the systems with respect to their thermal, acoustic, air permeability, water tightness and wind resistance features, as well as mechanical calculations of wind and snow loading and microventilation.

### **CORTIZO reliability**








# FAÇADES

## SYSTEMS

- 6 TP 52 Façade
- 8 SG 52 Façade
- 10 TPH 52 Façade
- 12 TPV 52 Façade
- 14 ST 52 Façade
- 16 SST 52 Façade
- 18 Equity Façade
- 20 Ventilated Façade
- 22 Millennium Façade
- 24 Solar Protection: Louvres
- 26 Lattices – Decorative Louvres





## TP 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects by using integral solutions.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to all of the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners, polygonals) as well as resolving large and heavy glazing modulations.

This **TP 52 façade** is a traditional system, also known as the Stick system. The fixing of the glazing to the supporting profiles is carried out by way of a continuous pressure profile screwed externally to a screw port incorporated in the mullions and transoms. The glazing remains fixed at its 4 sides using this profile that is available with separating gaskets in order to impede contact between the glazing and the metal. The pressure profile and the screws are covered by a continuous external embellishing profile known as a cover.

Great thermal breaking, together with an ample glazing capacity of up to 50 mm with glass compositions of large thicknesses and energy efficiency, gives to this new range of façades many excellent thermal and acoustic features.

Its seen external section coincides with the interior, being 52 mm





# TP 52 Façade

## Transmittance

Ucw from 0.6 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 50 mm.

Minimum glazing: 4 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12152:2000): Class AE

Water tightness  
(EN 12154:2000): Class RE<sub>1500</sub>

Wind resistance  
(EN 13116:2001): APT  
(design loading 2000 Pa- security loading 3000 Pa)  
Test reference 3,00 x 3,50 m.

Certification **CWCT** British Standard



## Internal seen section

## Profile thickness


Mullion 52 mm.

2,1 & 3,0 mm.

Transom 52 mm.

2,1 mm.

6, 12 & 30 mm stackable and thermally broken profiles



## Covers

85 mm deep elliptical cover.


H shape cover, 34 mm deep.

Rectangular cover: 14, 19 100 & 145 mm deep

Pyramid shape cover, 155 mm deep



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.

Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.

## SG 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners and polygonals) as well as resolving large and heavy modulations.

This **SG 52 façade** is a traditional system, also known as the Stick system. The fixing of the glazing to the supporting profiles is carried out by using clips. This system requires an insert that is fitted in to the glazing chamber (U profile). The combination of the clip and the insert allows the glass to be fastened on all four sides.

Great thermal breaking, together with an ample glazing capacity of up to 44mm with glass compositions of large thicknesses and energy efficiency, gives to this new range of façades many excellent thermal and acoustic features.

It has a “glass only” style on the exterior.





# SG 52 Façade

## Transmittance

Ucw from 0.6 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 44 mm.

Minimum glazing: 6 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12152:2000): Class AE

Water tightness  
(EN 12154:2000): Class RE<sub>1500</sub>

Wind resistance  
(EN 13116:2001): APT  
(design loading 2000 Pa- security loading 3000 Pa)  
Test reference 3,00 x 3,50 m.

Certification **CWCT** British Standard



## Internal seen section

## Profile thickness




Mullion 52 mm.

2,1 & 3,0 mm.


Transom 52 mm.

2,1 mm.

6, 12 & 30 mm stackable and thermally broken profiles



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.

Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.

## TPH 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners and polygonals) as well as resolving large and heavy modulations.

This **TPH 52 façade** is a mixed system that evolved from the combination of the TP 52 and the SG 52 systems. It maintains the pairing of the pressure cover on the horizontal gaskets highlighting the line in this direction whilst the glazing fixing is achieved by way of clips and the U profile on its vertical edge.

Great thermal breaking, together with an ample glazing capacity of up to 44 mm with glass compositions of large thicknesses and energy efficiency, gives to this new range of façades many excellent thermal and acoustic features.





# TPH 52 Façade

## Transmittance

Ucw from 0.6 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 44 mm.

Minimum glazing: 6 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12152:2000): Class AE

Water tightness  
(EN 12154:2000): Class RE<sub>1500</sub>

Wind resistance  
(EN 13116:2001): APT  
(design loading 2000 Pa- security loading 3000 Pa)  
Test reference 3,00 x 3,50 m.

Certification **CWCT** British Standard



## Internal seen section

Mullion 52 mm.


Transom 52 mm.

## Profile thickness

2,1 & 3,0 mm.

2,1 mm.

6, 12 & 30 mm stackable and thermally broken profiles



## Covers


85 mm deep elliptical cover.

H shape cover, 34 mm deep.

Rectangular cover: 14, 19 100 & 145 mm deep



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.

Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.

## TPV 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners and polygonals) as well as resolving large and heavy modulations.

This **TPV 52 façade** is a mixed system that evolved from the combination of the TP 52 and the SG 52 systems. It maintains the pairing of the pressure cover on the horizontal gaskets highlighting the line in this direction whilst the glazing fixing is achieved by way of clips and the U profile on its vertical edge.

Great thermal breaking, together with an ample glazing capacity of up to 44 mm with glass compositions of large thicknesses and energy efficiency, gives to this new range of façades many excellent thermal and acoustic features.





# TPV 52 Façade

## Transmittance

Ucw from 0.6 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 44 mm.

Minimum glazing: 6 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12152:2000): Class AE

Water tightness  
(EN 12154:2000): Class RE<sub>1500</sub>

Wind resistance  
(EN 13116:2001): APT  
(design loading 2000 Pa- security loading 3000 Pa)  
Test reference 3,00 x 3,50 m.

Certification **CWCT** British Standard



## Internal seen section

## Profile thickness


Mullion 52 mm.

2,1 & 3,0 mm.

Transom 52 mm.

2,1 mm.

6, 12 & 30 mm stackable and thermally broken profiles




## Covers


H shape cover, 34 mm deep.

Rectangular cover: 14, 19 100 & 145 mm deep

Pyramid shape cover, 155 mm deep



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.

Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.



## ST 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners and polygonals) as well as resolving large and heavy modulations.

With this **ST 52 façade** the glass is glued to an aluminium frame using structural silicone. The fixing of the glass-frame set to the supporting profiles is done by using the system's clips.

The style characteristic of this system is to offer the same aspect, whether with fixed glazing or with practicables, both in the exterior as in the interior.

Its glass only external style is with an open groove and the first weather barrier being an EPDM gasket which is installed around the perimeter of each module. An overlap closes the space between the gaskets.





# ST52 Façade

## Transmittance

Ucw from 0.7 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 38 mm.

Mínimum glazing: 6 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12152:2000): Class AE

Water tightness  
(EN 12154:2000): Class RE<sub>750</sub>

Wind resistance  
(EN 13116:2001): APT  
(design loading 1200 Pa- security loading 1800 Pa)  
Test reference 3,00 x 3,50 m.





## Internal seen section


Mullion 52 mm.  
Transom 52 mm.

## Profile thickness

2,1 & 3,0 mm.  
2,1 mm.



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.  
Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.




## SST 52 Façade

A new generation of façade consisting of a base system with an ample range of mullions and transoms that provides answers to the different style and construction needs for architectural projects.

Its base profile range of 16 mm to 250 mm in mullions and 22.5 mm to 255.5 mm in transoms, and equally with the complementary accessories, are common to the new CORTIZO façades. The extensive profile range and their mechanical unions allows for all types of façades to be built (vertically, inclining, 90° corners, corners and polygonals) as well as resolving large and heavy modulations.

With this **SST 52 façade**, the glass is mechanically fixed to a perimetral frame and thanks to the existence of an external trim that ensures the stability of the glazing, there is no need for a chemical fixing with structural silicone which is needed with the ST 52 system.

Its external aspect is that of an open channel with an aluminium surrounding around the glass and the first weather barrier being an EPDM gasket which is installed around the perimeter of each module.





# SST 52 Façade

## Transmittance

Ucw from 0.8 (W/m²K)

Please consult dimensions and glass

## Glazing

Maximum glazing: 30 mm.

Minimum glazing: 6 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability

(EN 12152:2000): Class AE

Water tightness

(EN 12154:2000): Class RE<sub>750</sub>

Wind resistance

(EN 13116:2001): APT

(design loading 1200 Pa- security loading 1800 Pa)

Test reference 3,00 x 3,50 m.



## Internal seen section

Mullion 52 mm.


Transom 52 mm.

## Profile thickness


2,1 & 3,0 mm.

2,1 mm.

Thermal breaking 18 mm.



## Opening possibilities



Hidden projecting

## Maximum / Low dimensions

### Projecting opening

Max. Width (L) = 2.500 mm. Min. Width (L) = 550 mm.

Max. Height(H) = 2.500 mm. Min. Height (H) = 650 mm.

## Maximum weight

Projecting opening 180 Kg.

## Equity Façade

A light curtain walling system with thermal insulation.

With a seen internal section of only 18 mm, both in the mullion as well as the transom, this new façade system presents a minimalist style and slenderness allowing a total entry of light to the interior of the building.

The mullion and transom profiles equalize its depth giving rise to a flush assembly that provides uniformity to the internal style of the façade.

The glazing is achieved by fixing the glass using aluminium pressure covers, both in vertical as in horizontal, in such a way that the external view is 52 mm and internally is only 18 mm.





# Equity Façade

## Transmittance

Ucw from 0.6 (W/m²K)  
Please consult dimensions and glass

## Glazing

Recommended glazing is an externally tempered pane.  
Maximum recommended glazing is 40 mm


## Finishes

- Colour powder coating (RAL, mottled and rough)
- Wood effect powder coating
- Anti-bacterial powder coating
- Anodized



Internal seen section	Profile thickness
Mullion 18 mm.	2,6 mm.
Transom 18 mm.	2,6 mm.

Thermal breaking 24 mm.




## Covers

H shape cover, 34 mm deep.  
Rectangular cover:14, 19 & 100 mm deep



## Opening possibilities



Projecting

## Maximum dimensions

Projecting opening  
Max. Width (L) = 2.200 mm.  
Max. Height(H) =2.200 mm.

## Maximum weight

Projecting opening 140 Kg.  
Fixed light 400 Kg.

## Ventilated Façade

A double light façade system, structural or semi-structural in its external style.

It incorporates a 140 mm chamber between the external and internal glazing in order to allow for the natural ventilation of the façade, reducing the thermal transmission towards the interior and achieving large energy efficiency for the building.

Access to the chamber is possible by way of practicable openings that facilitate cleaning and maintenance.





# Ventilated Façade

## Transmittance

Ucw from 0,7 (W/m²K)

Please consult dimensions and glass

## Glazing

Recommended glazing is an externally tempered pane.

Maximum glazing:

- External: structural according to external glass weight  
semi-structural: 28 mm.
- Internal: 39 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating





Anodized




## Sections

Mullion 145 mm.

Transom 45 & 34 mm.



## Opening possibilities



Hidden projecting  
Open-in for access to the ventilation chamber.

## Maximum dimensions


Projecting opening  
Max. Width (L) = 2.200 mm.  
Max. Height(H) = 2.200 mm.

## Maximum weight

Projecting opening 140 Kg.  
Fixed light 400 Kg.



## Millennium Façade



# Millennium Façade

## Transmittance

Ucw from 0.8 (W/m²K)

Please consult dimensions and glass

## Glazing

Tempered glass must be used.

Minimum glazing: 8 mm.

Maximum glazing: 26 mm.

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating




Anodized



## Sections

Mullion 145, 170 & 210 mm.

Interior vertical section view 65 mm.



A light façade system with external glazing fixed with grampons and fixing pieces: ball & socket or fixed. The grampons are made from stainless steel and surround the ball & socket and following this the previously machined glazing is fixed.

The supporting structure where the grampons are fixed to, is made up solely of vertical aluminium profiles that are high in thickness and resistance and consequently construction solutions with large fixed lights between supports are achieved.

This system is complemented by other profiles and gaskets that help to realise the most varied construction solutions.



## Solar protection: Louvres



# Solar protection: Louvres

**Louvre types:**

Fixed  
Regulated at 0°, 15°, 30° & 45°  
Adjustable with motor

Louvre sizes	Maximum recommended length*	
	Fixed louvres	Adjustable louvres
120 mm.	1,8 m.	
145 mm.	2,0 m.	1,9 m.
190 mm.	2,5 m.	2,4 m.
250 mm.	3,0 m.	3,0 m.
300 mm.	3,5 m.	3,4 m.
400 mm.	4,2 m.	4,0 m.

\* Depending on project specifications, it is possible to reach a longer louvre length (please consult)

**Categories achieved at test centre**

**Wind loading resistance**  
(UNE 13659:2004): Class 6 (max.)

Test carried out according UNE 1932:2001

Reference test:	Louvres	Length
	120 mm.	1,8 m.
	145 mm.	2,0 m.
	190 mm.	2,5 m.
	250 mm.	3,0 m.
	300 mm.	3,5 m.
	400 mm.	4,2 m.


**Finishes**

Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized



**Profile thicknesses**

Louvres	Thickness
120 mm.	1,75 mm.
145 mm.	1,80 mm.
190 mm.	2,50 mm.
250 mm.	2,75 mm.
300 mm.	3,45 mm.
400 mm.	3,80 mm.



A solar protection system for façades. This system of extruded aluminium louvres allows the light to be regulated and achieves notable savings in interior reffridgeration due to the creation of shaded zones that reduce the need for energy in those areas.

In order to cover a variety of requirements, there are louvres of distinct dimensions that can adapt to all types of project.

This is a system with 2 louvre types: fixed and adjustable. The first type presents regulating possibilities in gradient with angles of 0°, 15°, 30° & 45°. The adjustable louvres also have an option to be motorized and as an option the regulating mechanism can be hidden which then allows the possibility of having an aesthetically pleasing clear façade.

The louvre that is used is shaped elliptically and can be placed vertically or horizontally. This individual elliptical shape not only allows that the less beneficial effects of solar light are avoided but also works as a decorative architectural element. This solar protection system is particularly adequate for areas of great dimensions such as façades or curtain walls.



## Lattices-Decorative louvres





# Lattices-Decorative louvres

**Louvre types:**

- Lattices
- Decorative lattices
- Mini-lattices
- Tubular louvres
- Decorative louvres
- Façade covering louvres:
  - Punched
  - Square ondulated

Louvre types:	Maximum recommended length	Visibility coefficient
Lattices	2,0 m.	71% to 55°
Decorative lattices	1,5 m.	56% to 50°
Mini-lattices	1,3 m.	55% to 45°
Tubular louvres	2,0 m.	76% to 90°
Decorative louvres	6,5 m.	86% to 90°

\* Depending on project specifications, it is possible to reach a longer louvre length (please consult)

**Categories achieved at test centre**

**Wind loading resistance**

Lattice (test reference 2,0 metres)  
(UNE 13659:2004): Class 6 (max.)










Mini-lattice (Test reference 1,3 metres)  
(UNE 13659:2004): Class 5

Tubular louvres (Test reference 1,3 metres)  
(UNE 13659:2004): Class 6 (max.)

Tests carried out according to UNE 1932:2001 norms

**Finishes**

- Colour powder coating (RAL, mottled and rough)
- Wood effect powder coating
- Anti-bacterial powder coating
- Anodized



Extruded aluminium louvres designed for external and internal building finishing and looking for light and visibility control but always at the same time allowing for ventilation from one side to the other in the installation.

Ideal for courtyards, wall finishing, habitually used spaces etc.





# COMPOSITE PANEL SYSTEM





## Composite Panel

This ventilated façade system is manufactured directly in the composite panel production centre that Cortizo has in Spain. This factory, with a daily production capacity of 5,400 m<sup>2</sup>, guarantees the storage and immediate supply of this system in the various panel types and their finishes

Additionally, fabrication centres – with the latest generation of pantographs that are situated in production and distribution centres throughout Europe, facilitate the delivery of this constructive solution according to the modulation specifications that are defined in each of the projects.

Technical Departments that are exclusive for this product provide personalised help that is integral and specific in every architectonic project which includes Cortizo Composite Panel.

### Certificates:



Spain



Great Britain



Poland



France



Furthermore, to ensure the quality in the assembly systems, the manufacturing and fabrication processes of the composite panel are certified by way of ISO 9001.



# Composite Panel

## Categories achieved at test centre

A efficient, economic, stylish and sustainable construction solution for re-covering building façades that are made up of 2 aluminium sheets joined by a nucleus of thermoplastic resins.

A composite panel comprising of an external layer of aluminium alloy triple coated with PvdF paint (polyvinyl flouride) that offers great resistance to corrosion and ageing. The internal nucleus is made up of thermoplastic resins (polyethelene).

This material union provides the composite panel with some excellent mechanical properties: high impact resistance, increased rigidity and reduced weight. It is a product designed and tested to integrate in to buildings with increased thermal and accoustic features.

### Fire reaction classification

**FR - B-s-1,d0**

(according to EN-13501-1:2007 norm)

### Transmittance

**PE-U<sub>st</sub>(W/m²K) = 3,38**

**FR-U<sub>st</sub>(W/m²) = 5,62**

For a panel dimensioned at 1,48 x 1,23 m.

Test according to EN ISO 12567-1:2000 norm

### Accoustic insulation

**RW (C;Ctr)(dB):(C;Ctr) = 26 (-1;-3)**

For a panel dimensioned at 1,23 x 1,48 m.

Test according to EN ISO 140-3:1995 norm

### Finishes

**Painted in 22 solid & metallic colours in stock.**

Pure White	Shadow grey	Metallic silver
Arctic White	Dark green	Metallic champagne
Garnet	Brown	Metallic bronze
Intense red	Black	Metallic Titanium
Orange	Ultramarine blue	Carbon
Traffic yellow	Metallic White	Metallic blue
Beige	Grey metallic	Jade green
		Metallic copper

**All other RAL colours available on request**



### Panel types:

**PE-** standard (4mm. panel thickness - Al 0,5 m.)

**FR** – fire retardant (4mm. panel thickness - Al 0,5 m.)

**INTDESIGN-interiors** (3mm. panel thickness - Al 0,3 m.)

### Aluminium alloys

3005H44 / 3105H44 / 3105H46 / 5005H22

**Panel weight :** **PE-** 5,46 Kg/m<sup>2</sup> **FR-** 8,02 Kg/m<sup>2</sup>  
**Intdesign-** 3,85 Kg/m<sup>2</sup>

The composite panel is also available with the fire retardant option denominated FR (Fire Retardancy), that guarantees answers with respect to hypothetical fires. It is a 4 mm panel made up of 0,5 mm thick aluminium sheets, coated with PvdF paint with a thickness of 25/35 microns on the external face and a central nucleus consisting of a mineral composition and 3 mm thick polyethelene.

This range is completed with the INTDESIGN 3 mm thick panel which is ideal for internal applications, signage, digital printing, stands etc.

### Certificates

- Spain: **DIT**
- Great Britain: **BBA**
- Poland: **Wyrób budowlany**
- France: **CSTB**

### Fixing systems



**CH**  
Hanging system




**SZ**  
Male-Female system




**Riveted system**



**Glued system**



**CH-Hanging system**



**Riveted system**

### Sheet dimensions


		Width	Length
PE	Stock	1000-1250-1500	4000-5000
	Made to measure	1000-1250-1500	(Min/max) 2000/6000
FR	Stock	1000-1250-1500	4000-5000
	Made to measure	1000-1250-1500	(Min/max) 2000/6000
INTDESIGN	Stock	1500	3050-5050
	Made to measure	1000-1250	(Min/max) 2000/6000





# SKYLIGHT – VERANDA – SLIDING ROOF SYSTEMS

34 Skylight – Veranda  
36 Sliding Roof





## Skylight-Veranda

A new generation of skylights and verandas made up of a base system with a wide range of mullions and transoms that resolve the different aesthetic and constructive requirements for the architectonic requirements using integral solutions that permit the achievement of new spaces with great luminosity.

The base profiles consist of mullions from 130 mm to 250 mm and transoms from 40.5 mm to 255.5 mm as well as the complementary accessories that are common to all of the CORTIZO range of new façades.

The Thermal Breaking area, together with an ample glazing capacity of up to 50 mm with glass compositions of large thicknesses and energy efficiency, gives to this new range of skylights and verandas, many excellent thermal and accoustic features.

The profile design with first, second and third level mullions and transoms, allows the possibility of different water escape levels that guarantee perfect drainage and ventilation, and in this way it ensures total weather tightness.

- It allows the possibility of making skylights for gabled and hipped roofs and for the integration in the verandas of hinged and sliding series in its vertical facing.

Option of a motorized projecting opening in covered areas.





# Skylight-Veranda

## Transmittance

Ucw from 0.6 (W/m²K)

Please consult dimensions and glass

## Glazing

**Fixed lights:** Maximum - 50 mm.  
Minimum- 24 mm.

**Roof window:** Maximum - 46 mm.  
Minimum- 24 mm.

**Minimum incline** Pt= 12% (7°)

**Maximum incline** Pt= 85% (40°)

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized




## Internal seen section

Mullion 52 mm.  
Transom 52 mm.

## Profile thickness

2,1 & 3,0 mm.  
2,1 mm.



## Opening possibilities



**Open out:** Projecting – covered motorization



## Sliding Roof System


A sliding and automatic adjustable roof system designed to provide maximum comfort and well being, and a combination of style, robustness, convenience and features.

This type of finishing allows that the dwelling is enjoyed to its maximum in whatever season of the year.

With great 24 mm glazing capacity it allows for the integration of high resistance glazing luminosity in order to avoid the greenhouse effect and glazing capable of guaranteeing maximum acoustic insulation in the interior.

With a maximum opening of 66% of the surface area, this system provides ventilation and a total entry of light from above.

It has all types of complementary profiles to facilitate water collection and drainage that guarantee total water tightness with respect to rain.



# Sliding Roof System

### Pending

Profiles prepared for an inclination of 8,5° (15%)

### Glazing possibilities

- 25 mm cellular polycarbonate.
- 24 mm panel sandwich.
- 24 mm glass. (4 tempered/ 12 /4+4)

**Maximum light coverage:** 4.800 mm.

**Minimum light coverage:** 3.100 mm.

**Light width:** Unlimited when joining modules

### Categories achieved at test centre

#### Non flood covered area watertightness

Class APT

During the 6 hr. test, end of test and 24 hrs. following the same, no drips or humidity were detected in the enclosed area.  
Test reference: 4300 x 41600 mm in 3 adjustable rows, 9 sashes and 4/12/4+4 glass

#### Finishes

Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti bacterial paint  
Anodizing

#### Motorized sash openings

**Maximum opening being 66% of the area**





### Sections

Frame 133 mm.  
Sash 28 mm.

### Profile thickness

Sashes 1,5 mm.



### Opening possibilities



Example of 2 sashes 1 fix & 4 falls

### Slider:

2 sashes 1fix module and multiple falls

### Maximum dimensions

Width (L)= 2.300 mm. (polycarbonate and panel sandwich)  
1.200 mm. (glass)  
Height(H) = 1.600 mm.

### Maximum weight

75 Kg.






# HINGED

*With thermal break*

- 40 **Cor-Urban CC**
- 42 **Cor-70 CC16**
- 44 **Cor-70 Hidden Sash CC16**
- 46 **Cor- Galicia Premium Aluminium/timber**
- 48 **Cor-80 Industrial**
- 50 **Cor-70 Industrial**
- 52 **Cor-70 Hidden Sash**
- 54 **Cor-60**
- 56 **Cor-3500**
- 58 **Millennium FR Door**
- 60 **Millennium Plus Door**

*Without thermal break*

- 62 **Cor-2000**
- 64 **Cor-2300**
- 66 **Millennium 2000 Door**



## Cor-Urban CC System with thermal break

A hinged hidden double sash 122 mm system that allows for quadruple glazing facilitating a total acoustic silence and an optimum thermal insulation.

There is the possibility of incorporating a manual or motorized venetian blind or shutter in the internal (65 mm) chamber. Also access to the chamber is possible for cleaning and maintenance.

Additionally there is a quadruple gasket system that improves the thermal and acoustic insulation





# Cor-Urban CC System with thermal break

## Transmittance

Uw from 1,2 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing:

-external sash 22 mm.

-internal sash 30 mm.

Maximum acoustic insulation **Rw=50 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability

(EN 12207:2000): Class 4

Water tightness

(EN 12208:2000): Class E1650

Wind resistance

(EN 12210:2000): Class C5

Reference test 1,23 x 1,48 m. 1 sash



## Sections

Frame 122 mm.

Sash 121 mm.


## Profile thickness

Window 1,6 mm.

## Polyamide strip length

Frame 35 mm.

Sash 20 mm.



## Opening possibilities



## Open in:

-practicable 1 or 2 sashes

-turn-tilt 1 or 2 sashes

## Maximum dimensions/sash

Width (L) = 1.400 mm.

Height (H) = 1.700 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

150 Kg.

## Cor-70 CC16 System with thermal break

A hinged 70 mm window system with a potent insulation capacity and with a transmission value from only 0,8 W/m<sup>2</sup>K which has been achieved thanks to the perfect combination and design of aluminium profiles, 35 mm tubular polyamide rods, E.P.D.M tubular water tightness gaskets and a system of polyolefine foam that is fitted around the glazing space perimeter.

Possibility of straight and chamfered sashes and straight, chamfered or curved beads.

With its large glazing capacity of 58 mm it presents to this system some excellent acoustic and thermal features allowing the use of large glazing thicknesses and energy efficiencies.

Allows for the possibility of incorporating hardware with concealed hinges.





# Cor-70 CC16 System with thermal break

### Transmittance

Uw from 0,8 (W/m²K)  
Please consult typology, dimensions and glass

### Acoustic insulation

Maximum glazing: 58 mm.  
Maximum acoustic insulation **Rw=46 dBA**

### Finishes

Possibility of dual colour  
Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized

### Categories achieved at test centre



Air permeability  
(EN 12207:2000): Class 4  
Water tightness  
(EN 12208:2000): Class E1500  
Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,23 x 1,48 m. 2 sashes




**Sections**  
Frame 70 mm.  
Sash 75 mm.

**Profile thickness**  
Window 1,5 mm.  
Door 1,7 mm.

**Polyamide strip length** 35 mm.



### Opening possibilities



**Open in:** practicable, turn-tilt, folding, parallel tilt, hinged.

**Open out:** practicable, projecting-sliding.

### Maximum dimensions/sash

Width (L) = 1.600 mm.  
Height (H) = 2.800 mm.  
Please consult regarding maximum weight and dimensions according to types

### Maximum weight/sash

150 Kg.

## Cor-70 Hidden Sash CC16 System with thermal break

A 70 mm hinged hidden sash window system capable of uniting thermal features and profile slenderness.

Thanks to its profile design, it maintains the sash totally hidden from the outside in such a way that it is impossible to distinguish between the fixed zones that the opening has and is achieved by minimizing the seen profile section up to 70 mm which then maximizes the window glazing surface.

Allows for the possibility of incorporating hardware with concealed hinges.





# Cor-70 Hidden Sash CC16 System with thermal break

## Transmittance

Uw from 1,3 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 35 mm.

Maximum acoustic insulation **Rw=45 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class E1500

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,30 x 1,55 m. 1 sash



## Sections



Frame 70 mm.  
Sash 69 mm.

## Profile thickness


Window 1,5 mm.

## Polyamide strip length

Frame 35 mm. Sash 16 & 20 mm.



## Opening possibilities



## Open in:

- practicable 1 or 2 sashes
- turn-tilt 1 or 2 sashes
- hinged
- parallel tilt

## Maximum dimensions/sash

Width (L) = 1.600 mm.  
Height (H) = 2.800 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

150 Kg.

## Cor-Galicia Premium Aluminium Timber System with thermal break

A development of the Cor Galicia Premium series which is a mixed composite system comprising of aluminium and timber with thermal break and has a 66.4 mm frame depth which maintains the use of standard hardware and offers the possibility of triple adjustment and front fixing.

It has a similar shape but with an improved thermal and acoustic performance over the previous system version and is about a more economic window to fabricate by simplifying this phase and reducing the necessary manufacturing time by between 15 to 20%.

It is made up of external aluminium profiles that are assembled with 14.6 & 16 mm polyamide strips that make up the thermal breaking zone and improves notably its thermal insulation and being able to reach minimum window transmission values of 1.1 (W/m<sup>2</sup>K).

The joining of the external aluminium frames and the internal timber mouldings can be carried out in two ways: by fixing independently with clips (this allows for the substitution of the mouldings and the possibility of other timber treatments that are different to those normally supplied) and by way of assembly using an EPDM gasket. In both cases, this assembly ensures a perfect absorption of the different material expansions.





# Cor-Galicia Premium Aluminium Timber System with thermal break

## Transmittance

Uw from 1,3 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 40 mm.(Sash)  
30 mm.(Fix)

Maximum acoustic insulation **Rw=40 dBA**

## Finishes

### Aluminium

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

### Interior timber:

American Oak, Sapelly, Mellis Pine and other timber options available on order

(all of which are treated with an ecological varnish that is without dissolvent and is satin and transparent).

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class 9A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,23 x 1,48 m. 2 sashes



## Sections

Frame 66,4 mm.

Sash 85,3 mm.




## Profile thickness

Window 1,5 mm.

Door 1,6 mm.

## Polyamide strip length

Frame 14.8 mm. Sash 16 mm.



## Opening possibilities



**Open in:** practicable, turn-tilt  
parallel tilt, hinged.

## Maximum dimensions/sash

Width (L) = 1.400 mm.

Height (H) = 2.400 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

100 Kg.

## Cor-80 Industrial System with thermal break

A new concept of a Euro-Groove hinged system capable of reaching the maximum levels of weather tightness, energy saving and acoustic protection with reduced assembly and fabrication time.

With 80 mm of frame depth, it responds to the most severe climatic demands, and provides an unbeatable degree of energy efficiency thanks to its minimal window transmission value (UH) that can reach  $0.8 \text{ W/m}^2\text{K}$ . These minimum values are achieved thanks to the perfect design of the thermal break zone with 45 mm tubular polyamide strips as well as the incorporation of cross-linked polyolefin both in the glazing space as well as the interior of the frame and sash.

Its great glazing capacity of up to 65 mm allows for the use of energy efficient glazing and compositions of large thicknesses as well as double chambers that gives excellent thermal and acoustic performance (up to 46 dB of noise protection) that translates in to maximum energy saving and total interior comfort.

The performance achieved in the AEV test, has shown this window to have the best water tightness performance, air permeability and wind resistance in order to guarantee the greatest protection against the most adverse atmospheric agents.

The simplicity in its assembly and less labour time, allows for a more industrialized fabrication resulting in a final saving of time and cost.





# Cor-80 Industrial System with thermal break

## Transmittance

Uw from 0,8 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 65 mm.

Maximum acoustic insulation **Rw=46 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability

(EN 12207:2000): Class 4

Water tightness

(EN 12208:2000): Class E1950

Wind resistance

(EN 12210:2000): Class C5

Reference test 1,23 x 1,48 m. 2 sashes

Possibility of incorporating hardware with concealed hinges.

Possibility of incorporating security hardware Evo Security.



## Sections

Frame 80 mm.



Sash 88 mm.

## Profile thickness

Window 1,5 mm.

Door 1,7 mm.

Polyamide strip length 45 mm.



## Opening possibilities



**Open in:** practicable, turn-tilt, parallel tilt, hinged.

## Maximum dimensions/sash

Width (L) = 1.600 mm.

Height (H) = 2.600 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

120 Kg.



## Cor-70 Industrial System with thermal break

A hinged window system that was conceived with the object of satisfying the needs of a determined market segment for an economical window system, simple but versatile with many features.

With a 70 mm frame depth and Euro Groove opening gearing, this innovation from the R&D Department has thermal transmission from only 0,8 W/m<sup>2</sup>K in order to adapt to distinct climatic severities and material demands on energy efficiency.

Its simplicity in fitting and reduced need for labour allows for a more industrialised manufacture resulting with time and cost savings at the end.

It features a straight style in both sash and bead.

A glazing capacity of 55 mm that allows the use of energy efficient glazing and compositions with large thicknesses and affords this system excellent acoustic and thermal features.





# Cor-70 Industrial System with thermal break

### Transmittance

Uw from 0,8 (W/m²K)  
Please consult typology, dimensions and glass

### Acoustic insulation

Maximum glazing: 55 mm.  
Maximum acoustic insulation **Rw=44 dBA**

### Finishes

Possibility of dual colour  
Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized

### Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class E1200

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,23 x 1,48 m. 2 sashes

Burgular resistant  
(EN 1627:2011): Grade RC2 (WK2)  
Reference test 2,52 x 1,47 m. 1 sash  
with EVO SECURITY hardware




Possibility of incorporating hardware with  
concealed hinges.

Possibility of incorporating security hardware  
Evo Security.




Sections	Profile thickness
Frame 70 mm.	Window 1,5 mm.
Sash 78 mm.	Balcony 1,7 mm.

**Polyamide strip length** from 32 to 35 mm.



### Opening possibilities



**Open in:** practicable,  
turn-tilt, parallel tilt,  
hinged.

**Open out:** practicable,  
projecting-sliding.

### Maximum dimensions/sash

Width (L) = 1.500 mm.  
Height (H) = 2.600 mm.

Please consult regarding maximum weight and dimensions according to types

### Maximum weight/sash

120 Kg.

## Cor-70 Hidden Sash System with thermal break

A new Euro-Groove concealed sash window design with slim profiles that are characterized by a seen surface of only 66 mm from the exterior that maximises the glazing surface and is able to reach 85% of the total window glazing. This characteristic provides an extraordinary increase in luminosity in the inside of the dwelling.

Its design allows for the hidden sash to be maintained from the outside in such a way that it is impossible to distinguish from the fixed zones that the opening has and therefore achieving perfect homogeneity in the façade's style.

A 35 mm thermally broken area and the insertion of polyolefin sponge in the frame and sash allows it to reach values of up to 1,0 W/m<sup>2</sup>K of transmission in the space and therefore maximising its energy efficiency. These high thermal performances are completed with an increased level of sound insulation that this system achieves thanks to the possibility of installing glazing units of up to 40 mm in thickness.

The classifications achieved in the AEV tests go to prove that the system has excellent water tightness, air permeability and wind resistance values in order to obtain increased protection against the most unfavourable weather conditions.





# Cor-70 Hidden Sash System with thermal break

### Transmittance

Uw from 1,0 (W/m²K)  
Please consult typology, dimensions and glass

### Acoustic insulation

Maximum glazing: 40 mm.  
Maximum acoustic insulation **Rw=46 dBA**

### Finishes

Possibility of dual colour  
Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized

### Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4  
Water tightness  
(EN 12208:2000): Class E1650  
Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,23 x 1,48 m. 2 sashes




Possibility of incorporating hardware with concealed hinges.  
Possibility of incorporating security hardware  
Evo Security.




**Sections**  
Frame 70 mm.  
Sash 70 mm.

**Profile thickness**  
Window 1,9 mm.

**Polyamide strip length** 35 mm.



### Opening possibilities



**Open in:**  
Practicable 1 & 2 sashes,  
Turn-tilt 1 & 2 sashes  
Hinged

### Maximum dimensions/sash

Width (L) = 1.300 mm.  
Height (H) = 2.400 mm.  
Please consult regarding maximum weight and dimensions according to types

### Maximum weight/sash

120 Kg.



## Cor-60 System with thermal break





# Cor-60 System with thermal break

## Transmittance

Uw from 1,0 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 46 mm.

Maximum acoustic insulation **Rw=48 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

Air permeability

(EN 12207:2000): Class 4

Water tightness

(EN 12208:2000): Class E1200

Wind resistance

(EN 12210:2000): Class C5

Reference test 1,20 x 1,16 m. 2 sashes

Possibility of straight or curved sashes and beads

Possibility of incorporating hardware with concealed hinges.

Possibility of incorporating security hardware - Evo Security.



## Sections

Frame 60 mm.



Sash 68 mm.

## Profile thickness


Window 1,6 mm.

Door 1,6 mm.

Polyamide strip length 24 mm.



## Opening possibilities



**Open in:** practicable, turn-tilt, folding, parallel tilt, hinged.

**Open out:** practicable, projecting-sliding, pivoting on horizontal or vertical axis

## Maximum dimensions/sash

Width (L) = 1.500 mm.

Height (H) = 2.600 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

120 Kg.

**Cor-3500 System with thermal break**





# Cor-3500 System with thermal break

## Transmittance

Uw from 1,0 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 41 mm.

Maximum acoustic insulation **Rw=46 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability

(EN 12207:2000): Class 4

Water tightness

(EN 12208:2000): Class E1200

Wind resistance

(EN 12210:2000): Class C5

Reference test 1,20 x 1,20 m. 2 sashes

Possibility of straight or curved sashes and beads

Possibility of incorporating hardware with concealed hinges.

Possibility of incorporating security hardware - Evo Security.



## Sections

Frame 54 mm.



Sash 63 mm.

## Profile thickness


Window 1,5 mm.

Door 1,7 mm

Polyamide strip length 24 mm.



## Opening possibilities



**Open in:** practicable, turn-tilt, folding, parallel tilt, hinged.

**Open out:** practicable, projecting-sliding.

## Maximum dimensions/sash

Width (L) = 1.500 mm.

Height (H) = 2.400 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

120 Kg.

## Millennium FR Door System with thermal break

This new fire resistant door system that has a fire resistance classification of EI<sub>2</sub>60, resolves the security requirements in case of fire, allowing for the compartmentalization in fire sectors in the building and the evacuation of the users.

Comprising of 80 mm section straight line coplanar profiles, 2.2 mm thick and a 35 mm thermal breaking zone, it offers a 60 minute fire resistance time thanks to the utilisation of retardant insulation materials that do not combust in the profile chambers as well as intumescent gaskets that dilate and bio-soluble paper in the glass area.

With a transmission value from 1,4 W/m<sup>2</sup>K, it reaches unbeatable thermal features and with its large glazing capacity having a free space of 48 mm, it guarantees a maximum acoustic insulation.

Possibility of joining with fixed lights, incorporation of opening gearing with anti-panic function, automatic door closers and handles/hinges officially approved in the sectoring of fires.





# Millennium FR Door System with thermal break

## Transmittance

Uw from 1,4 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 48 mm.

Maximum acoustic insulation **Rw=38 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Fire resistance and smoke control

Test carried out according to norms  
EN 1364-1:2000 and EN 1634-1:2010



**CLASS EI<sub>2</sub>60 - C5**

Classification according to norm UNE-EN 13501-2:2009+A1:2010  
(C5= 200.000 test cycles)

Door test reference 1,35 x 2,35 m. 1 sash  
Glass EI60 single glazed 23 to 25 mm.






## Sections

Frame 80 mm.  
Sash 80 mm.


## Profile thickness

Door 2,2 mm.

Polyamide strip length 35 mm.



## Opening possibilities



**Open in:** practicable  
1 or 2 sashes.  
**Open Out:** practicable  
1 or 2 sashes.

## Maximum dimensions/sash

Width (L) = 1.500 mm.  
Height (H) = 2.600 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

240 Kg.

## Millennium Plus Door System with thermal break

Coplanar door entry system with straight 70 mm and thermally broken for commercial premises and buildings.

With a transmission value from only 0.9 W/m<sup>2</sup>K, it reaches unbeatable thermal features and its great glazing capacity guarantees a maximum acoustic insulation.

Possibility of high resistance hinges (face fix or re-inforced in to the channel) capable of supporting up to 220 kgs in weight per sash.

Possibility of hidden hinges with maximum dimensions and weight per sash of 2700 mm in height, 1500 mm in width and 120 kgs. and with a maximum sash opening of 100°.

It presents solutions of finishing to the floor and compatible meeting styles with our actual systems.

It is valid as a configuration for an emergency exit with anti-panic devices according to EN 179 & EN 1125 norms.

There is also the option of incorporating an automatic mechanism or its motorization that allows automatic hinged openings.





# Millennium Plus Door System with thermal break

## Transmittance

Uw from 0.9 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 54 mm.

Maximum acoustic insulation **Rw=38 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability (EN 12207:2000): **Class 4**

Water tightness (EN 12208:2000): **Class 6A**

Wind resistance (EN 12210:2000): **Class C4**

Door test reference 1,20 x 2,30 m. 1 sash

## Resistance to mild impact

Test carried out according to norm EN 13049:2003

**CLASS 5 (max)**

Test on door reference 1,80 x 2,20 m. 2 sashes. Laminated glass 3+3

## Resistance to repeated openings and closings

Test carried out according to norm EN 1191:2000

**500.000 cycles**

Test on door reference 0,935 x 2,10 m. 1 sash



## Sections




Frame 70 mm.

Sash 70 mm.


## Profile thickness

Door 2,0 mm.

Polyamide strip length 24 mm.



## Opening possibilities



**Open in:** practicable  
1 & 2 sashes.

**Open Out:** practicable  
1 & 2 sashes.

**Automatic opening:** internal and  
external hinged single sash

## Maximum dimensions/sash

Width (L) = 1.800 mm.

Height (H) = 3.000 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

220 Kg.

120 Kg.(hidden hinges)



Cor-2000 System





# Cor-2000 System

## Transmittance

Uw from 1,8 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 30 mm.

Maximum acoustic insulation **Rw=39 dBA**

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class 9A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,20 x 1,18 m. 2 sashes

Possibility of straight or curved sashes and beads



Possibility of incorporating hardware with concealed hinges.

Possibility of incorporating security hardware - Evo Security.




Sections <http://box.cortizo.com/ficheros/compartir/Y29ydGl6b19jYXJwZXRhczg5MQ>  
Frame 45 mm. Profile thickness  
Sash 53 mm. Window 1,5 mm.  
Door 1,7 mm

Possibility of straight or curved beads



## Opening possibilities



**Open in:** practicable, turn-tilt, folding, parallel tilt, hinged.

**Open out:** practicable, projecting-sliding, pivoting on horizontal or vertical axis, swing opening

## Maximum dimensions/sash

Width (L) = 1.500 mm.  
Height (H) = 2.400 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

120 Kg.



## Cor-2300 System





# Cor-2300 System

## Transmittance

Uw from 2,0 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 26 mm.

Maximum acoustic insulation **Rw=39 dBA**

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class 9A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,105 x 1,210 m. 2 sashes

Possibility of straight or curved sashes and beads

Possibility of incorporating hardware with concealed hinges.

Possibility of incorporating security hardware - Evo Security.



## Sections



Frame 40 mm.

Sash 48 mm.


## Profile thickness

Window 1,3 mm.

Door 1,4 mm



## Opening possibilities



**Open in:** practicable, turn-tilt, folding, parallel tilt, hinged.

**Open out:** practicable, projecting-sliding, pivoting on horizontal or vertical axis

## Maximum dimensions/sash

Width (L) = 1.500 mm.  
Height (H) = 2.400 mm.

## Maximum weight/sash

120 Kg.

Please consult regarding maximum weight and dimensions according to types

## Millennium 2000 Door System

45 mm coplanar door system for commercial premises and buildings.

Available in 2 versions:


- **Millenium 2000 door:** with face fix hinges and 2 or 3 high resistance pins capable of supporting up to 180 kg. per sash.

-**Millenium 2000 automatic door:** Allows doors to be made for automatic opening sliders. This new solution that optimises the stay spaces, has been specifically designed to resolve entrances with high transit (offices, shopping centres, hospitals...) as it guarantees good pedestrian circulation as well as security in emergency situations.

This automation for a slider also gives the option of using minimal seen section profiles.

Possibility of 1 or 2 sashes, with or without fixed lights, presenting the double option of a motor in order to generate the opening: one at 12 cm. high and another being minimalist at only 7 cm high.

There is also the option of incorporating an automatic mechanism or its motorization that allows automatic hinged openings.





# Millennium 2000 Door System

## Transmittance

Uw from 2,3 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 30 mm.

Maximum acoustic insulation **Rw=38 dBA**

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Resistance to mild impact

Test carried out according to norm  
EN 13049:2003

**CLASS 5 (max)**

Test on door reference 1,80 x 2,20 m. 2 sashes  
Laminated glass 3+3




## Sections



Frame 45 mm.  
Sash 45 mm.

## Profile thickness


Door 2,0 mm.



Automatic version



## Opening possibilities



**Open in:** 1 & 2 sashes.  
**Open out:** 1 & 2 sashes.  
**Swing opening:** 1 & 2 sashes.

## Automatic opening:

- sliding of 1 & 2 sashes.
- practicable in and out of 1 sash.

## Maximum dimensions/sash

Width (L) = 1.450 mm.  
Height (H) = 3.000 mm.

Please consult regarding maximum weight and dimensions according to types

## Maximum weight/sash

180 Kg.  
120 Kg. Automatic version





# SLIDING


## WINDOW AND DOOR SYSTEMS

*With thermal break*

- 70 Cor-Vision Sliding
- 72 4600 Lift and Slide HI
- 74 4500 Lift and Slide
- 76 4200 Sliding

*Without thermal break*

- 78 2000 Perimetral Sliding



## Cor-Vision Sliding System with thermal break

An avant-garde design of a thermally broken sliding system that permits maximum luminosity with the minimum amount of seen aluminium profile section. An elegance in design that looks to cover great light spaces with minimum frame fragments of between 9-14% of the total surface. It shows seen centre junction sections of only 20 mm, in the lateral junction at 77 mm and the top/bottom junctions at 57 mm.

Possibility of inlaying the bottom, top and lateral frames.

Possibility of sash meetings at a 90° corner without a mullion.

In its monochannel version, comprising of fixed and sash, the hidden rail is found in the fixed area.

It incorporates the new type of **GALANDAGE** that is designed to allow the possibility of an integral opening in the space to completely conceal the sashes in the building curtain wall chamber. In this way a 100% opening surface can be achieved.

This **GALANDAGE** option is made up of a single and dual channel rail which allows for a single or double sash concealed balcony doors.

This presents a new type of frame for 1, 2 or 3 rails that allows the incorporation of a stainless steel rail that affords increased sliding smoothness, an increase in loading support for the bearings (up to 320 kg/sash) and increased durability.

A system with traditional fitting procedures with perimetral frame and sashes that allows the sash to be dismantled in case of glass breakage, damage to the aluminium profile etc. It incorporates a rod operated multipoint lock.





# Cor-Vision Sliding System with thermal break

## Transmittance

Uw from 1,3 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 30 mm.

Maximum acoustic insulation **Rw=41 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class 7A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,23 x 1,55 m. 1 sash + 1 fixed light






## Sections

Frame 116 mm.  
182 mm. 3 rails  
Sash 37 mm.


## Profile thickness

Door 1,7 mm.

**Polyamide strip length** from 16 mm. to 24 mm.



## Opening possibilities



## Maximum dimensions

Width (L) = 4.400 mm.  
Height (H) = 3.000 mm.

2 sashes door

Please consult regarding maximum weight and dimensions for other opening types

## Maximum weight/sash

320 Kg.

## 4600 Lift and Slide HI System (High Insulation) with thermal break

A new lift and slide door system that exhibits the best thermal insulation in all the sliding range with unbeatable transmission values ( $U_w$ ) from  $0.9 \text{ (W/m}^2\text{K)}$

This maximum energy efficiency is possible thanks to the perfect combination of a thermal breaking zone with 35 & 24 mm polyamide strips and cross-linked polyethylene as well as the possibility of large glazing allowed by the sashes and up to 55 mm thick glass which allows for the option to install compositions of double and triple chamber glass in order to guarantee its exceptional thermal insulation and particularly this system will improve noise protection.

The possibility of large sash dimensions makes this system ideal for enclosing large spaces and guaranteeing internal luminosity without foregoing the maximum thermal and acoustic performances.

This slider bases its workings on a system where the sashes are mounted on a mechanism that allows for it to be elevated when opened and to drop down when closed in such a way that the closed door rests over lower and lateral longitudinal weather gaskets and can be fixed in whatever position and in this way improving its weather tightness and acoustic insulation. It is a robust system in appearance but light at the same time with an ultra smooth opening action and perfect sash sliding over a stainless steel rail that avoids wear and tear.

It offers a modern design with a straight style both in sashes and beads.





# 4600 Lift and Slide HI System (High Insulation) with thermal break

### Transmittance

Uw from 0.9 (W/m²K)  
Please consult typology, dimensions and glass

### Acoustic insulation

Maximum glazing: 55 mm.  
Maximum acoustic insulation **Rw=43 dBA**

### Finishes

Possibility of dual colour  
Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized

### Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 4

Water tightness  
(EN 12208:2000): Class 9A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 4,0 x 2,4 m. 2 sashes



### Sections


Frame 160.6 mm.  
251mm. 3 rails  
Sash 70 mm.

### Longitud varilla poliamida


Frame 35 mm. Sash 24 mm.

### Profile thickness

Door 2,0 mm.



### Opening possibilities



Sliding of 2, 3, 4 & 6 sashes.  
Possibility of 3 rails.

### Maximum dimensions

Width (L) = 6.700 mm.  
Height (H) = 3.200 mm.  
2 sashes door

Please consult regarding maximum weight and dimensions for other opening types

### Maximum weight/sash

400 Kg.

## 4500 Lift and Slide System with thermal break

A perimetral sliding door system with thermal breaking and a bevelled or curved style both in sashes and beads.

There are two versions:

- **4500 lift and slide** that bases its operation on a system in which the sashes are fitted with a mechanism that permits its own elevation whilst opening and descending when closing in such a way that the closed door rests over the top and bottom longitudinal water tightness gaskets allowing it to be fixed in whatever position.

Possibility of corner sash meeting at 90° without mullions.

In the fixed light and sash configuration, the rail in the fixed zone remains hidden.

- **4500 in line slider** allows the sliders to be made economically in large dimensions.

It presents configurations of sash+fixed light, Fixed light+sash+fixed light, 2 sashes+2 fixed lights and 4 sashes.

The rail where the sashes slide along is made of stainless steel in order to avoid wear and tear.





# 4500 Lift and Slide System with thermal break

## Transmittance

Uw from 1,5 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 30 mm.

Maximum acoustic insulation **Rw=42 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 3

Water tightness  
(EN 12208:2000): Class 8A

Wind resistance  
(EN 12210:2000): Class C4  
Reference test 1,85 x 2,05 m. 1 sash + 1 fixed light



## Sections

Frame 100/123/127 mm.

185 mm. 3 rails

Sash 51 mm.



## Profile thickness

Door 2,0 mm.


## Polyamide strip length

-Lift version of 24 & 14.6 mm.

-In-line version of 30 & 14.6 mm.



## Opening possibilities



Sliding of 2, 3, 4 & 6 sashes.  
Possibility of 3 rails.  
Possibility of 1 rail.  
(1 sash + 1 fixed light)  
Possibility of corner sash at 90° without mullions.

## Maximum dimensions

Width (L) = 6.700 mm.

Height (H) = 2.900 mm.

2 sashes door

Please consult regarding maximum weight and dimensions for other opening types

## Maximum weight/sash

400 Kg.(Lift version)

280 Kg.(In-line version )



## 4200 Sliding System with thermal break

A versatile system with multiple perimetral frames and the possibility of head or perimetral sashes.

This presents a stylish option with curved or straight sashes. In its version of straight head sashes, the **GALANDAGE** 4200 Slider solution is included. It is designed to allow the possibility of an integral opening in the space to totally hide the sashes in the building's curtain wall chamber. This achieves a 100% opening surface.

The **GALANDAGE** option allows a single rail and dual rail frame allowing for balcony systems with 1, 2 & 4 hidden sashes.

It also allows for the incorporation of one sash in parallel hidden from the Tamiz solar protection system.





# 4200 Sliding System with thermal break

## Transmittance

Uw from 1,5 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 26 mm.

Maximum acoustic insulation **Rw=39 dBA**

## Finishes

Possibility of dual colour

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

Air permeability  
(EN 12207:2000): Class 3

Water tightness  
(EN 12208:2000): Class 7A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,20 x 1,20 m. 2 sashes




## Sections

Frame 60/65/77/80 mm.  
106/126 mm. 3 rails  
Sash 33 & 37 mm.


## Profile thickness

Window 1,5 mm.

**Polyamide strip length** from 14,6 to 20 mm.



## Opening possibilities



Slider of 2, 3, 4 & 6 sashes.  
Possibility of 3 rails.  
Possibility of single or dual rail galandage in 1, 2 & 4 sashes.

## Maximum dimensions

Width (L) = 4.400 mm.  
Height (H) = 2.600 mm.

2 sashes window

Please consult regarding maximum weight and dimensions for other opening types

## Maximum weight/sash

100 Kg. (Perimetral sash)  
200 Kg. (Head sash)

## 2000 Perimetral Sliding System

A perimetral sliding system with the possibility of straight, bevelled and curved sashes.





# 2000 Perimetral Sliding System

## Transmittance

Uw from 2.9 (W/m²K)

Please consult typology, dimensions and glass

## Acoustic insulation

Maximum glazing: 17 mm.

Maximum acoustic insulation **Rw=33 dBA**

## Finishes

Colour powder coating (RAL, mottled and rough)

Wood effect powder coating

Anti-bacterial powder coating

Anodized

## Categories achieved at test centre

Air permeability  
(EN 12207:2000): Class 3

Water tightness  
(EN 12208:2000): Class 8A

Wind resistance  
(EN 12210:2000): Class C5  
Reference test 1,20 x 1,20 m. 2 sashes



## Sections

Frame 40 mm. 1 rail

40, 45, 60 & 70 mm. 2 rails

80 mm. 3 rails


Sashes 26 mm. (straight)

26 mm. (chamfered)


27,5 mm. (curve)

## Profile thickness

Window 1,5 mm.



## Opening possibilities



Sliding of 2, 3, 4 & 6 sashes.  
Possibility of 3 rails.  
Possibility of 1 rail.

## Maximum dimensions

Width (L) = 3.200 mm.  
Height (H) = 2.600 mm.

2 sashes window

Please consult regarding maximum weight and dimensions for other opening types

## Maximum weight/sash


100 Kg.





# SOLAR PROTECTION SYSTEMS

82 Tamiz



## Tamiz System

A counter-window system with fixed or adjustable louvres.





# Tamiz System

## Transmittance

Thermal resistance of the counterwindow and the thermal chamber  $\Delta R= 0,08 \text{ (m}^2\text{K/W)}$

Uw (W/m²K)	Uws (W/m²K)
0.8	0.75
1.0	0.93
1.2	1.09
1.4	1.26
1.6	1.42
1.8	1.57
2.0	1.72
2.2	1.87
2.4	2.01
2.6	2.15
2.8	2.29
3.0	2.42
3.2	2.55

Uw window transmittance  
Uws transmittance of the window-counterwindow assembly

Calculations according to EN ISO 10077-1:2000

## Categories achieved at test centre

**Wind loading resistance**  
(UNE 13659:2004): CLASS 5

Test reference 1,50 x 1,50 m. 2 sashes

## Finishes

Colour powder coating (RAL, mottled and rough)  
Wood effect powder coating  
Anti-bacterial powder coating  
Anodized

## Closing possibilities:

Closing with fixed or adjustable louvres  
Opaque closing (panel sandwich)  
Glazed closing




## Sections


Frame 47 mm.  
Sash 40 mm.

## Profile thickness

Window 1,3 mm.  
Door 1,5 mm.



## Opening possibilities



Practicable 1, 2, 3 & 4 sashes  
Folding  
Slider

## Maximum dimensions

Width (L) =1.600 mm.  
Height (H) = 2.500 mm.  
single sash

Please consult regarding maximum weight and dimensions for other opening types

## Maximum weight/sash


65 Kg.





# BALUSTRADING

System



## View Glass Balustrade

Minimalist balustrading system which combines the most trend setting esthetic with the highest demands in safety.

It consists of a system in "U" designed to lodge laminated safety glass and which can be fixed to wrought iron or to the edge of the iron work.

The View Glass system withstands a stress of 1.0 kN/m applied at 1.1 meters of the bottom. Therefore, according to the Eurocode 1, it is suitable for use in the areas A, B, C1, C2, C3, C4 and E.





# View Glass Balustrade

## Possibilities

- Bar balustrading
- Bar balustrading with top edge

## Finishes

- Colour powder coating (RAL, mottled and rough)
- Wood effect powder coating
- Anti-bacterial powder coating
- Anodized

## Maximum height

1.100 mm.


Tests according to UNE 85237:1991, UNE 85.238:1991 and UNE 85240:1990 norms, requirements established in Eurocode 1 according to EN 1991-1-1:2003 /AC: 2010

- 1 – Static horizontal test towards the exterior.
- 2 – Static horizontal test towards the interior.
- 3 – Dynamic test with mild object.
- 4 - Dynamic test with hard object.
- 5 – Verification of the specifications of the Eurocode according to the table 6.12 for categories of use of 1kN/m.

CLASSIFICATION ACCORDING TO UNE 85240:1990:  
**Class A-EXCELLENT**

Reference test on the balustrading with extruded aluminum and glass, with top free edge bar at total height 1100mm. (H) x 1500mm. (L)

Reference test on the balustrading with extruded aluminum and glass, at total height 1100mm. (H) x 1500mm. (L)




## Glass

GLASS	
COMPOSITION	TYPE
15 - 1.52 - 10	LAMINATED GLASS
8 - 1.52 - 8	
6 - 1.52 - 6	

## Balustrading System

A balustrading system that allows for the contemplation of all types of solutions thanks to an extensive range of accessories that complement the system.

Possibility of fixing to wrought iron work or to the edge of the iron work.





# Balustrading System

## Possibilities

- Glass Balustrading
- Glass Balustrading with free top edge
- Bar Balustrading
- Bar Balustrading with top edge

## Handrail possibilities

- Square - 60 mm. width
- Circular - 66 mm diameter
- Elliptical - 80 mm. external perimeter

## Finishes

- Colour powder coating (RAL, mottled and rough)
- Wood effect powder coating
- Anti-bacterial powder coating
- Anodized




## Tests according to EN 85.237-1991 norms EN 85.238-1991 & EN 85.240-1990

- 1-Static horizontal test towards the exterior
- 2-Static horizontal test towards the interior
- 3-Static vertical test
- 4-Dynamic test with mild object
- 5-Dynamic test with hard object
- 6-Security test

(EN 85.240:1990): Class A- EXCELLENT

Reference test on the balustrading with glass at total height 1.100 mm.(H) x 2.450 mm.(L) and 3 pilasters.

Reference test on the balustrading with top free edge bar of 1100 mm (H) x 2000 mm (L) and 3 pilasters



## Maximum dimensions between pilasters

1.000 mm.


## Minimum height

900 mm.





# ACCESSORIES





WINDOW WITH HIDDEN HINGES



## Accessories

CORTIZO has a complete range of accessories designed to respond to the most demanding and up to date architectural and interior design needs.

With a variety of basic minimalist aesthetics and with multiple finishes, they guarantee a perfect integration of accessory and profiles resulting in a configuration of a harmonious and modern enclosure.

As well as the standard accessories, there is also the possibility of integrating **HARDWARE WITH HIDDEN HINGES** in to the following systems:

COR 70 CC16 / COR 70 Hidden Sash CC16 / COR 60 CC16 / COR 80 Industrial / COR 70 Industrial / COR 70 Hidden Sash / COR 60 / COR 60 Hidden Sash / COR 3500 / COR 3000 / COR 2000 / COR 2300 / Millennium Plus Door

Additionally, many of the systems allow for the option of incorporating **SECURITY HARDWARE** , Evo Security:

COR 80 Industrial / COR 70 Industrial / COR 70 Hidden Sash / COR 60 / COR 60 Hidden Sash / COR 3500 / COR 3000 / COR 2000 / COR 2300



### CORTIZO STAINLESS HANDLE

#### DESIGN AND STYLE

Window handle in stainless steel for practicable openings and turn/tilt of avant-garde design.

Perfect adaptability to the transmission box and multi-point lock. With a minimum escutcheon design (66 x 31 x 10.5 mm), hidden screws and 7 mm spindle, this handle has the following dimensions: 158 mm long and 31 mm wide.

Materials: Handle and escutcheon made from stainless steel and rose with a nylon base.

**Finishes:** •Stainless steel



### CORTIZO HANDLE

#### DESIGN WITHOUT ESCUTCHEON

An aluminium handle for practicable openings and turn/tilts, and with its straight style and its almost complete absence of an escutcheon, it converts in to an ideal accessory to integrate in to whatever Cortizo hinged window.

Perfect adaptability to the transmission box and the multi-point lock. With hidden screws and a 7 mm spindle, this handle has the following dimensions: 147.5 mm in length and 30.4 mm in width.

**Finishes:**

- Powder coated White/Black/Inox
- Powder coated Matt Silver/Bright silver
- RAL colour chart
- Special textured coatings
- Inox PVD
- Gold PVD







# DIRECTORIES

114 **CENTRAL HEADQUARTERS**  
Spanish distribution & logistic centres

115 **International distribution and logistic centres**







## PRODUCTIVE CENTRES

### HEADQUARTERS

Extramundi, s/n  
15901 Padrón (A Coruña)  
España  
Tel.: +34 981 804 213  
Fax: +34 981 81 60 25  
www.cortizo.com

### STA. CRUZ DE TENERIFE FACTORY

Pol. Ind. Granadilla – Parc. 8/12  
38611 Granadilla de Abona  
(Tenerife)  
Tel.: +34 922 392 532  
Fax: +34 922 392 289  
canarias@cortizo.com

### CIUDAD REAL FACTORY

Pol. Ind. Calle D – Parc. 20  
13200 Manzanares  
(Ciudad Real)  
Tel.: +34 926 647 050  
Fax: +34 926 611 675  
manzanares@cortizo.com

### SLOVAKIA FACTORY

Zeleznicný rad, 29  
986 01 Nová Bana  
Slovakia  
Tel.: +421 456 855 402  
Fax: +421 456 855 257  
cortizo\_slovakia@cortizo.com

### POLAND FACTORY

Ul. Geodetów, 2  
97-500 Radomsko  
Poland  
Tel.: +48 44 683 55 55  
Fax: +48 44 683 55 56  
systemy.polska@cortizo.com

## Spanish distribution & logistic centres

### ÁLAVA

Pol. Ind. Galzar  
C/ Arrikruz, 46. Aptdo. 24  
01200 – Salvatierra  
Tel.: 945 300 977  
Fax: 945 300 983  
alava@cortizo.com

### ASTURIAS

Pol. Ind. Porceyo I-12  
Camín del Fontán 214  
33392 – Porceyo- Gijón  
Tel.: 985 169 954  
Fax: 985 167 049  
gijon@cortizo.com

### ALUMINIOS PÉREZ SOTO, S.L.

Pol. Ind. Rocas, 4  
C/ Antonio Gaudí Cornet, 2  
33211 – Gijón  
Tel.: 985 168 744  
Fax: 985 168 299

### BALEARES

MADERESA – MALLORCA  
Cami Vell de Ciutat, 58-B, P.I.  
07630 – Campos  
Tel.: 971 160 328  
Fax: 971 651 283  
mallorca@maderesa.net

### MADERESA – MENORCA

Pol. Ind. La Trotxa, P. 37  
07730 – Alaior  
Tel.: 971 379 170  
Fax: 971 379 171  
menorca@maderesa.net

### MADERESA – IBIZA

Móvil: 618 498 435  
ibiza@maderesa.net

### BURGOS

Polígono de Villalonquén  
C/ Condado de Treviño, 18  
09001 – Burgos  
Tel.: 947 297 550  
burgos@cortizo.com

### CÁCERES

ALUVISA  
Ctra. de Medellín, km 2 izda.  
10196 – Cáceres  
Tel.: 927 242 373 / 223 630  
Fax: 927 242 373  
aluvisa@aluvisa.es

### CANTABRIA

Avda. de la Cerrada, 37  
Nave 13  
39600 – Maliaño  
Tel.: 942 260 733  
Fax: 942 260 763  
santander@cortizo.com

### CIUDAD REAL

Pol. Ind. Calle D – Parc. 20  
13200 Manzanares  
(Ciudad Real)  
Tel.: 926 644 883  
Fax: 926 644 776  
manzanares@cortizo.com

### FUERTEVENTURA

Pol. Ind. El Matorral  
Pol. 3 Nave 32  
35610 El Matorral – Antigua  
Tel.: 928 160 434  
Fax: 928 160 444  
fuerteventura@cortizo.com

### GRAN CANARIA

Pol. Ind. Arinaga. Fase I  
C/ Las Mimosas,  
Parc. 117-118  
35119 Agüimes  
Tel.: 928 188 916  
Fax: 928 188 917  
grancanaria@cortizo.com

### LANZAROTE

C/ Nicolás Estebanes  
Nave 3-4  
Barriada de Tenorio  
35500 Arrecife - Lanzarote  
Tel.: 928 804 112  
Fax: 928 805 084  
lanzarote@cortizo.com

### LEÓN

Ctra. León-Zamora, km. 8,5  
24231 – Onzonilla  
Tel.: 987 211 507  
Fax: 987 216 320  
leon@cortizo.com

### LLEIDA

Pol. Ind. de Cervera  
Calle Pla d'urgell, Parc. 7-8  
25200 – Cervera  
Tel.: 973 533 037  
Fax: 973 531 252  
cervera@cortizo.com

### LUGO

Pol. Ind. del Ceao  
C/ Vidrio, 116. 27290 – Lugo  
Tel.: 982 209 616  
Fax: 982 209 616  
lugo@cortizo.com

### MADRID

Pol. Ind. Regordño  
C/ Regordño, 10  
28936 – Móstoles  
Tel.: 91 643 51 00  
Fax: 91 646 26 92  
cortizomadrid@cortizo.com

### OURENSE

Pol. Ind. Barreiros  
Ctra. Madrid, km. 530. Nave 13  
32911 San Cibrao das Viñas  
Tel.: 988 247 628  
Fax: 988 239 841  
ourense@cortizo.com

### VALENCIA

INDUSTRIA AMARRO, S.A.  
C/ Ciudad de Sevilla, 13  
46988 – Paterna  
Tel.: 961 340 611  
Fax: 961 340 780

### VALLADOLID

ALUMINIOS HERNANSANZ, S.L.  
Pol. Ind.. San Cristobal  
C/ Helio, 22  
47012 – Valladolid  
Tel.: 983 236 004  
Fax: 983 479 110  
herca@aluminiosherca.com

### ZAMORA

Pol. Ind. Morales del Vino  
Ctra. Salamanca, Km. 3  
49190- Morales del Vino  
Tel.: 980 574 047  
Fax: 980 574 046  
zamora@cortizo.com

### ZARAGOZA

Pol. Ind. Malpica – Alfindén  
C/ Chopo, 72  
50171 La Puebla de Alfindén  
Tel.: 976 108 346  
Fax: 976 108 098  
zaragoza@cortizo.com



## International distribution and logistic centres

### GERMANY (EAST) & AUSTRIA

**MIGUEL A. PIÑEIRO**  
Tel.: +49 16 094 830 097  
export@cortizo.com

### BELGIUM, HOLLAND GERMANY (WEST) & SWITZERLAND

**DIDIER HANSSENS**  
Av. du Cyclotron, 6  
B-1348 Louvain-la-Neuve (Belgium)  
Tel.: +32 1039 0093/44  
Fax: +32 1039 0094  
dh@hanssens-alusteel.com

### CROATIA, SERBIA, MONTENEGRO, BOSNIA-HERZEGOVINA, MACEDONIA & SLOVENIA

**SRADAN BASARIC**  
Vicenta iz kastva, 4  
10000 – Zagreb (Croatia)  
Tel.: +385 95 9081 294  
Fax: +385 1 3840 035  
centraleurope@cortizo.com

### DENMARK & NORWAY

**NICHOLAS V. SCHÖNBUCHER**  
Delken 42, DK - 6000 Kolding (Denmark)  
Tel.: +45 20 521 918  
denmark@cortizo.com

### SLOVAKIA & CZECH REPUBLIC

Architectural Systems Delegate  
**BOHUS GORDAN**  
Železničný rad, 29  
968 01 – Nová Baňa (Slovakia)  
Tel.: +421 456 855 402  
systemy.slovensko@cortizo.com  
sales\_mngt\_slovakia@cortizo.com

Moravia Area (Czech Republic)  
**RATISLAV MARUSKA**  
Tel.: +420 773 502 644  
cesko@cortizo.com

Bohemia Area (Czech Republic)  
**Alucad Bohemia**  
Rohoznice, 104  
Lázně Bohemia (Czech Republic)  
Tel.: +420 469 631 113  
info@alucad.cz

Industrial profile Delegate  
**MARIAN HONAIZER**  
Železničný rad, 29  
968 01 – Nová Baňa (Slovakia)  
Tel.: +421 262 250 226  
Fax: +421 262 250 324  
Mobile: +421 915 986 159  
sales\_slovakia@cortizo.com

### FINLAND

**EDUARD MAANDI**  
Tel.: +35 850 341 8000  
finland@cortizo.com

### FRANCE (NORTH)

**STÉPHANE HEMMER**  
66 Avenue H. Barbusse  
94240 L'Hay les Roses (France)  
Mobile: +34 669 376 981  
Fax: +34 981 804 212  
francianorte@cortizo.com

### FRANCE (SOUTH)

**JESÚS ZAFRILLA**  
Impasse des Charmilles  
26100 Romans sur Isère (France)  
Tel.: +33 475 052 387  
Fax: +33 475 053 203  
Mobile: +33 607 767 698  
cortizo@zafrilla.eu

### GREAT BRITAIN

**ALAN GRADY**  
Quedgeley West Bus Park  
Gloucester GL2 4PA (GB)  
Tel.: +44 1 452 723 355  
Fax: +44 1 452 723 300  
sales@visionprofiles.co.uk

### HUNGARY

Architectural Systems Delegate  
**MARIAN BODIS**  
Železničný rad, 29  
968 01 – Nová Baňa (Slovakia)  
Tel.: +421 456 855 402  
Mobile: +36 202 482 430  
muszakiosztaly@cortizo.com

Industrial profile Delegate  
**BODIS MIKULAS**  
Železničný rad, 29  
968 01 – Nová Baňa (Slovakia)  
Tel.: +421 456 855 402  
Mobile: +36 309 372 804  
hungaria@cortizo.com

### BALTIC STATES: Estonia, Latvia & Lithuania

**DMITRI SVIRIDOV**  
Tel.: +37 253 338 500  
baltic@cortizo.com

### POLAND

Architectural Systems Delegate  
**ARKADIUSZ BERLINSKI**  
Geodetów  
97-500 Radomsko (Poland)  
Tel.: +48 44 683 55 55  
Fax: +48 44 683 55 56  
systemy.polska@cortizo.com

### Industrial profile Delegate

**ARTUR SKERCZYNSKI**  
Ul. Wolodyjowskiego, 23  
05 092 Lomianki (Poland)  
Tel.: +48 227 517 425  
Mobile: +48 603 250 090  
polska@cortizo.com

### PORTUGAL

**VILA DO CONDE - PORTO**  
Architectural Systems Delegate  
**RAMÓN CAROU TUBÍO**  
Zona Industrial de Varziela  
Rua nº 8, lotes 30-31  
4480 Fajozes- Vila do Conde (Portugal)  
Tel.: +351 252 637 598  
Fax: +351 252 637 599  
Mobile: +351 914 399 113  
dptotecnico.viladoconde@cortizo.com


**RIO MAIOR - LISBONE**  
Architectural Systems Delegate  
**ANTONIO CASAL LAFUENTE**  
Parque de Negocios de Rio Maior,  
Rua E - Lote 10  
Quinta do Sanguinhal  
2040-357 – Rio Maior  
Tel.: +351 243 909 430  
Fax: +351 243 907 259  
riomaior@cortizo.com

**GAIA AREA**  
**MARIA & MARINA-Aluminios e Componentes, Lda.**  
Travessa do Agro, 46  
4410-384 Arconzelo- Vila Nova Gaia (Portugal)  
Tel.: +351 22 7622275 / +351 22 7622276  
Fax: +351 22 7622277  
geral@mariamarina.com

Industrial profile Delegate  
**JUAN CARLOS TARRIO**  
Mobile: +351 914 399 116  
comercialportugal@cortizo.com

### ROMANIA

**Timisoara Area**  
**DAN TUDOR**  
Calea Buziasului, Nr.11  
300714-Timisoara (Romania)  
Tel.: +40 356 111 053  
timisoara@cortizo.com



**Cluj-Napoca Area**  
**COSMIN PAUNESCU**  
Strada Oasului, Nr. 27  
400264 Cluj-Napoca (Romania)  
Tel.: +40 364 113 047  
Mobile: +40 745 025 551  
cluj@cortizo.com

**Bacau Area**  
**DAN RATOI**  
Calea Republicii, Nr.159  
Tel.: +40 234 585 318  
Mobil: +40 742 023 400  
600303 Bacau (Romania)  
bacau@cortizo.com

**Bucarest Area**  
**NICU FLORESCU**  
Calea Alea Floresasca, Nr.169A, Corp A,  
Etaj 4, Birou 2027  
Sector 1, 014472 - Bucuresti  
Tel.: +40 749 238 794  
bucuresti@cortizo.com

Industrial profile Delegate  
**FLORIN ANTONIO SUDRIJAN**  
Piata Traian Nr 5  
555600 Ocna Sibului (Romania)  
Móvil: +40 744 281 197  
Tel.: +40 726 550 537  
romaniacortizo@cortizo.com

### SWEDEN

**PASKO SARIC**  
Jungfrudansen 26  
S-17165 Solna (Sweden)  
Tel.: +46 (0)841 069 001  
Tel.: +46 (0)707 336 011  
scandinavia@cortizo.com

### UKRAINE

**PAVLO OPALKO**  
Pryrichna Str. B 29, Fl 18  
04213 Kyiv (Ukraine)  
Tel.: +38 097 816 4073  
ukraine@cortizo.com







[www.cortizo.com](http://www.cortizo.com)

{ DOWNLOAD OUR APP }



AVAILABLE FOR SMART PHONE AND TABLET



**CORTIZO AR**  
DISCOVER AUGMENTED REALITY

